




PROFIL TRANSVERSAL TIP



- imbracaminte din beton de ciment 22 cm- NEO14-2002
- folie polietilena conform STAS 8171
- strat nisip pilonat 5 cm conform STAS 662/2002
- amestec optimal cu piatra sparta 0-63 mm, 35 cm executata conform STAS 667
- geogriile cu ochiuri 30x30 mm si noduri fixe
- strat nisip pilonat 7 cm conform STAS 662/2002

Verificator/ Expert	Nume	Semnatura	Cerinta	REFERAT/EXPERTIZA NR./DATA	
Beneficiar: <b>AMBRO S.A.</b> Calea Unirii nr. 24 Suceava, tel. :0230 205 000 fax :0230 205 111 email:office@ambro.ro				Denumire Proiect:  "Cresterea eficienței energetice operaționale la AMBRO S.A. Suceava prin implementarea unei instalații de cogenerare de înalta eficiență" Locația: Suceava, Calea Unirii, Nr.24, Jud. Suceava	Pr. 397/19
Proiectant general: <b>S.C. LOIAL IMPEX S.R.L.</b>  J33/27/1993 C.F: R3176126 Str. Oborului, Nr.75A, Scheia Com. Scheia, jud. Suceava, cod 720182 Tel. 0230/526800;Fax: 0230/526900; Mobil: 0722/220645 E-mail: office@loial.ro					
Proiectant de specialitate rezistenta: <b>S.C. MOLDPROIECT A.S.D. S.R.L.</b>  J33/27/1993 C.F: R3176126 Str. Mihail Sadoveanu, Nr.9A, Oras Suceava, jud. Suceava, cod 720013 Tel./Fax 0330/803501;E-mail: moldproiect@yahoo.com				Proiect Amenajare Exterioara	Faza:  <b>PT+DE</b>
Specificatie	Nume	Sem.	Scara 1:50	Denumire Plansa:  Profil transversal tip	Plansa nr.  <b>D3</b>
Sef proiect	Ing.C. Vieru				
Sef proiect rezistenta	Ing.arh. B. Adomnitei		Data: 08.2019		Rev0
Proiectat	Ing. A. Ieremie				
Desenat	Ing. A. Ieremie				